Volvo Retail Sustainable Experience (VRSE) Showroom Concept

Sales - Room Datasheets

Generic VRSE Concept
VCI Equivalent (VRSE) Specification

Version no.
2

Prepared by Meda
www.experiencemeda.com
The Granary, Church Lane
Steventon, Oxfordshire
OX13 6SW

Issued by Volvo Car Ireland.
For additional copies of this Datasheet,
a copy of the Outline Specifications
or to report any discrepancy, please
email james@experiencemeda.com

VOLVO

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Contents

4.1
Introduction to the
Sales Outline Specifications
Comprising:

4.1.1 Introduction to the VRSE Scheme
4.1.2 VRSE Planning Principles - ground floor
4.1.3 VRSE Planning Principles - mezzanine
4.1.4 VRSE Planning Principles - external elevations
4.1.5 VRSE Planning Principles - internal elevations
4.1.6 VRSE Planning Principles - site plan
4.1.7 VRSE Planning Principles - parking bay types (1)
4.1.7 VRSE Planning Principles - parking bay types (2)
4.1.8 VRSE Planning Principles - ground floor layout
4.1.9 VRSE Planning Principles - The Street layout
4.1.10 VRSE Planning Principles - The Living Room layout
4.1.11 VRSE Planning Principles - first floor layout

4.2
Generic planning / finishes / fittings
Comprising:

4.2.1 A. External finishes
4.2.2 B. External finishes
4.2.3 C. External finishes
4.2.4 A. Internal finishes / fittings
4.2.5 B. Internal finishes / fittings
4.2.6 C. Internal finishes
4.2.7 D. Digital elements
4.2.8 Ground Floor floor finishes plan
4.2.9 First Floor floor finishes plan
4.2.10 Ground Floor ceiling finishes plan
4.2.11 First Floor ceiling finishes plan

4.3
External Details
Comprising:

4.3.1 Shop Windows
4.3.2 Customer Entrance

4.4
Internal Sales Details
Comprising:

4.4.1 General Reception
4.4.2 Consultation Points
4.4.3 Accessories Hub / Accessorised Vehicle
4.4.4 Internal Selekt Certified Display
4.4.5 Your Car Studio
4.4.6 Consultation Rooms
4.4.7 Lifestyle Shop
4.4.8 The Living Room
4.4.9 Clean Water Station / Coffee Point
4.4.10 Sales Consultants' office
4.4.11 Sales / Business Managers' office
4.4.12 Car Delivery Bays
4.4.13 A - Customer Facilities - Toilets
4.4.13 B - Customer Facilities - Coats Cupboard
4.4.14 Front of House Kitchen Facilities & Cleaner's Cupboard
4.4.15 Front of House Staircase

4.5
Internal Staff Area Details
Comprising:

4.5.1 Staff Toilets
4.5.2 Staff Canteen
4.5.3 eLearning Room
4.5.4 Typical office
4.5.5 Meeting Room
4.5.6 Typical Manager's office
4.5.7 Comms Room

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Section 4.1

Introduction

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**



Introduction

Supporting your VRSE Retailer scheme

These Sales - Room Datasheets have been prepared in order to support you in the development and delivery of your VRSE Retailer scheme.

The Datasheets are intended as an 'illustrated guide' to the areas and rooms of the sales areas and should always be read in conjunction with the Outline Specifications documents and the Outline Specifications Appendices (which can be found online.)

Please note that this document covers all aspects of the Sales operations.

For Aftersales operations in relation to Aftersales areas, Workshops and VPS (Volvo Personal Service) please refer to the Aftersales - Room Datasheets document.


Please further note that these documents will be updated as and when required.

Always look for the version number, to ensure you have the current issue.

All the latest versions are available at

https://vci.medastandards.com

- Outline Specifications - New Build / Major Refurbishments
- Supplier Appendices
- Sales - Room Datasheets
- Aftersales - Room Datasheets.




Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

The VRSE Interior Planning Principles

Plan illustration.
Not to scale



VRSE Areas

Whilst some areas may appear familiar to current retail partners, there have been a number of updates with the introduction of the current global VRSE design.

Each area has a series of set pieces designed for a specific purpose aligned to the Global Retailer Standards. These areas have specific titles and associated furniture, finishes and fixtures.

Whilst every Retailer layout will vary, these areas are mandatory elements of the VRSE programme and require to be planned for accordingly.

Key:

1.	Shop Windows
2.	Customer Entrance
3.	The Street
4.	General Reception
5.	Consultation Points
6.	High Consultation Point
7.	Accessories Hub
8.	Accessorised Vehicle
9.	Internal Selekt Certified Display
10.	The Living Room
11.	Your Car Studio
12.	Consultation Rooms
13.	Lifestyle Shop
14.	Clean Water Station / Coffee Point
15.	Customer facilities
16.	Car Delivery Bays (with E.V. Charging Point)
17.	Sales Consultants office
18.	Sales / Business Managers' office
19.	Service Customer Meeting Points
20.	Service Managers' office
21.	Workshop Support / Warranty office
22.	Staff stair and accessible lift to mezzanine

NB: Please refer to Aftersales - Room Datasheets for all details regarding No. 19. Service Customer Meeting Points, No. 20. Service Manager and No. 21. Workshop Support / Warranty office.


Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

The VRSE Interior Planning Principles

Plan illustration.
Not to scale



NB: Please refer to Aftersales - Room Datasheets for the layout plan and all details regarding the following mezzanine accommodation not shown here:

Staff canteen, Male technicians facilities, Female technicians facilities, Plant, back of house stair to workshop.

Key:


1.	Brand Managers' office
2.	Finance office
3.	Accounts office
4.	General administration office
5.	Marketing / Product Specialists / Sales administration office
6.	Training / meeting room
7.	e-Learning rooms
8.	Staff toilets
9.	Comms room
10.	Store / archive
11.	Staff stair and accessible lift to showroom areas

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**


VOLVO


Meda


The VRSE external elevations




Key to external elevations










Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO


Meda

The VRSE internal elevations




Key to internal elevations

A




B



C




D



Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

Generic layout



VRSE areas

This schematic site plan illustrates the required areas, bay count and generic planning principles according to the VCI VRSE programme.

Key:

1. Plaza / Customer parking bays
2. Demonstrator display bays
3. Selekt Certified Used vehicle display bays
4. Selekt Certified Used vehicle display bays under canopy
5. Non-franchise used vehicle display bays
6. Courtesy car parking bays
7. Trade parts customer parking bays
8. Service WIP bays
9. New vehicle storage bays
10. Software download bay
11. Staff parking bays
12. Cycle racks
13. Parts van parking area
14. Battery storage
15. Waste storage

Charging points key:

- 11kW
- 22kW
- 13 Amp
- 175kW DC Fast Charger

NB: Designated charging bays as per VCI VRSE Specification.

Please note that the external charging points indicated are double headed units ie: will serve 2 bays.


It is the responsibility of the Retailer to ensure that the number of charging points and total kW / Amps meet VCI mandated standards.


Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda


Customer parking indicative setting out (relevant to the generic layout site plan)





1. Accessible bay
2. Parent and child bay
3. Standard parking bay
4. Demonstrator display bay
5. Selekt Certified Used display bay
6. Non-franchise used display bay
7. Trade parts customer parking bay.

Charging bay types




- 11kW
- 22kW
- 13 Amp
- 175kW DC fast charger

NB: Designated charging bays as per VCI VRSE Specification.

It is the responsibility of the Retailer to ensure that the number of charging points and total kW / Amps meet VCI mandated standards.

Storage bay types




1. Customer parking bay (back up)
2. Demonstrator parking bay (back up)
3. Staff parking bay
4. New vehicle stock parking bay
5. Service WIP bay
6. Software download bay

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO


Meda

Feature display areas



1. Selekt Certified Used Cars podium (optional)
2. New vehicle podium (optional)
3. Selekt Certified Used Canopy

Landscaping and cycle parking




1. Low level soft landscaping
2. High level soft landscaping
3. Cycle parking

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO


Meda

Floor plan



A Indicates loose-laid rug ● Indicates 11kW charger

Reflected ceiling plan




Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**


VOLVO

Meda


Floor plan



Reflected ceiling plan




Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**




Above: Floor plan

Below: Reflected ceiling plan




Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**



Above: Floor plan

Below: Reflected ceiling plan



Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Section 4.2

Generic planning / finishes / fittings

Datasheet 4.2 Finishes / fittings

Do not scale from these drawings

4.2.1 A. External finishes

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda



Volvo Sales: External finishes

Please note that external finishes required to the building envelope apply to both Greenfield and Brownfield or Refurbished sites.

External envelope

The typical façade will comprise of 1,200mm wide module.

Sales showroom frontage

Proprietary 'Technal MX Capped' or similar thermally insulated curtain wall system.

Shop Window

Proprietary frameless, jointless, double glazed 12mm leaf clear glazed (to nearest, full 1,200mm wide module of glazing over). Size 6,000 x 2,400mm high overall,
or
single-glazed, solid, jointless panes are acceptable if SBEM can accommodate heat losses.

Showroom Entrance Portal

Proprietary Entrance Portal formed with extruded aluminium sections finished to Interpon D2525 – Bleu 2700 Sable – Metallic Fine Texture YW353F with concealed integral flat roof and rain water drainage, LED lighting to front and rear reveals with opal acrylic lens – supplied and installed by Volvo specialist including Opening Hours sign on acrylic plaque to internal side wall.

NB: Contractor to include external scraper matt (FD2) aluminium frame with black rubber insert to external extent of entrance in recessed concrete plinth.

Mat-well edging in proprietary recessed frame set in concrete.

For all specification options please refer to the Outline Specifications documents.


Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

Key exterior features

Glazing



Showroom Entrance



Shop Windows



Selekt Certified Used external canopy



New vehicle podium



Selekt Certified Used Cars podium



Datasheet 4.2 Finishes / fittings

Do not scale from these drawings

4.2.3 C. External finishes

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

For all external specification options please refer to the Outline Specifications documents.

Glazing



Curtain wall

Proprietary aluminium frame, double glazed curtain wall system with 1,200mm wide modular frame width with external caps to be RAL 9003 Signal White.

Clear glazing to be filmed in proprietary dot matrix, translucent film on the interior pane.



Shop Window

Proprietary frameless, joint-less, double glazed 12mm leaf clear glazed, toughened, low E, low iron, Argon filled cavity glazing in single pane (to nearest, full 1,200mm wide module of glazing over).

Size 6,000 x 2,400mm high.



Showroom vehicle access doors


Inward opening folding stacking, top hung or sliding door in 1,200mm leafs with clear glazed sections. Stiles and frames be RAL 9003 Signal White externally and internally.



Car Delivery Bay vehicle access doors

Within curtain wall to be matching bi-fold glazed doors. Where within cladding elements, they should be fully glazed segmental shutter door, top hung and trimming steel or frames concealed within reveals and bulkheads. Stiles and frames to match external façades PPC finishes of RAL 9003 Signal White externally and internally.

Cladding



Cladding to showroom areas

External elevations on Sales elements may include Proprietary 1,000mm wide

insulated composite cladding system, vertically fixed on cladding rails, finished to RAL 9006 White Aluminium.

Showroom entrance




Showroom Entrance Portal

Proprietary Entrance Portal formed with extruded aluminium sections finished to Interpon D2525 – Bleu 2700 Sable – Metallic Fine Texture YW353F with concealed integral flat roof and rain water drainage, LED lighting to front and rear reveals.



Showroom entrance doors

Proprietary single or double glazed leafs of 12mm toughened glass, automatic opening sliding doors. Frameless glazed with PPC proprietary door stiles and frames RAL 9006 White Aluminium externally and RAL 9003 Signal White internally.



External scraper matt

Aluminium frame in anthracite finish with black textile brush strips to external extent of entrance in recessed concrete plinth.

Floor finishes



Plaza / customer parking / demonstrator display bays

80mm concrete block paving (to Civil Engineers design) with textured granite effect, 160 x 160mm (or 120 x 160mm). Colour - Silver Grey.

Parking bays in Silver Grey paved parking areas to be demarcated with full length charcoal paviours between bays.



Selekt Certified Used display area Area comprising brick paving of 100 x 200mm brick paviour. Colour - Char-coal.

Buffer soldier course half battered face edge paviours at junctions with black tarmac circulation lanes.



Building perimeter apron

Apron paving to building perimeter of brick paviour in sand bed. Colour - Charcoal.

Perimeter treatment



Bollards

Minimum 90mm diameter 750mm high stainless-steel post bollard set in concrete – including within apron paving at external corners of glazing /cladding, at pedestrian showroom entrances, vehicle entrances and entrances to the site.

Datasheet 4.2 Finishes / fittings

Do not scale from these drawings

4.2.4 A. Internal finishes

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda



Volvo Sales: Internal finishes

Please note that internal finishes required to the Sales and Aftersales areas apply to both Greenfield and Brownfield or Refurbished sites.

The internal showroom spaces are based on the VRSE principle of allocating 60% of the overall showroom area to The Street and 30% to The Living Room with the remaining 10% being taken up by Circulation.

The Street

All interior faces of the external glazing are to be finished to RAL 9003 Signal White.

Generally floor finishes are polished concrete with a surface treatment. Internal entrance matt with ribbed carpet insert.

Wall finishes are matt painted to RAL 9003 Signal White with the the exception of those areas indicated within the approved Green Pack where specific areas are highlighted with matt painted finish to RAL 7044 Silk Grey.

The Living Room

Generally floor finishes are polished concrete with a surface treatment and sheet carpet to offices.

Wall finishes are a combination of ‘ash’ vertical timber battens and paint finish to match RAL 9003 Signal White and RAL 7044 Silk Grey as indicated.

Offices and Consultation Rooms each have their own colour palette to differentiate these areas from the main Living Room spaces.

The above is a general summary of the approach to internal finishes. Please refer to the approved Green Design Pack specific to your site, individual generic room data sheets contained within this document and Outline Specifications documents for more detail.

Datasheet 4.2 Finishes / fittings

Do not scale from these drawings

4.2.5 B. Internal finishes / fittings

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

NB: Please refer to the Outline Specifications for full details


Ironmongery



Proprietary 'D-Line' satin stainless steel 'Lever Handle L' or 'Pull Handle Straight' from the Knud Holscher collection with matching ironmongery including coat hooks, door stops and kick plates, flush plates and soap dispensers. Hand driers or paper towel dispensers in satin stainless steel to match.

Glazing





V1 - Consultation Rooms and Sales Offices

Proprietary 'Komfort Polar' or 'PolarTec' frameless optical white low iron glazed screen and glass door with ironmongery as specified.

All glazing to include manifestation.

Any framing to top and base to be RAL 9003 Signal White to all faces.

V2 – Non-customer facing offices

Proprietary 'Komfort Polar' or 'PolarTec' with RAL 9003 Signal White finished glazed door panel with rebated frame.

All glazing to include manifestation.

GP1– Internal glazed screens

Proprietary 'Komfort PolarTec' or 'Polar Vision' frameless, highly transparent glass, fixed vertically.

Frameless double-glazed unit.

Typically fire-rated glazing between Sales and Aftersales.

All glazing to include manifestation.


Any framing to top and base to be RAL 9003 Signal White to all faces with the exception of the viewing window into the workshop - workshop face to be RAL 7037 Dusty Grey.

GP2 – Screen walls at Car Delivery

Proprietary 'Komfort PolarTec' or 'Polar Vision' frameless, highly transparent extra clear low iron glazed screen system, fixed vertically. All glazing to include manifestation.

Any framing to top and base to be RAL 9003 Signal White.

Ceiling finishes



CS1/CS1B - The Street friezes and bulkheads

'Gyproc Duraline MR or Duraline' painted MF gypsum ceiling. Matt finish to RAL 9003 Signal White or RAL 7044 Silk Grey as indicated.

CS3 - The Street

'Zentia Prestige' or similar 600 X 1200 tegular tile. Matt finish to RAL 9003 Signal White, grid in white PPC 15mm tee.

CS1A - Car Handover Suite Bay

'Gyproc Duraline MR or Duraline' painted MF gypsum ceiling. Matt finish to RAL 7037 Dusty Grey.

CS4 - Consultation Rooms, Offices and Meeting Rooms

'Zentia Prestige' or similar 600 X 600 tegular tile. Matt finish to RAL 9003 Signal White, grid in white PPC 15mm tee.

Ceiling margins where shown to achieve full tile ceiling grids symmetrically set out within the room should be finished as (CS1) painted MF gypsum ceiling. Matt finish to RAL 9003 Signal White.



CS6 - The Living Room areas

Proprietary 600 x 1,200mm lay in timber ceiling in real wood 'Ash' ribs at 20mm thick x 40mm deep and 30mm spacing gap.

Lay in timber ceiling to be supplied by VCI approved supplier only.

P3 Living area soffit behind open ceilings.

Ceiling (and all services / ducts) to be painted to RAL 9005 Jet Black matt finish

or

Black fabric mesh stapled to the back of the battens.

CT1 - Stores, Canteens and Techs facilities including Staff and Tech toilets

Suspended ceiling tile - 'Zentia Hydrabloc' or similar 600 x 600mm moisture resistant lay in grid system.

Standard white.


Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

NB: Please refer to the Outline Specifications for full details

Floor finishes




FD1 - Internal entrance mat.

Aluminium framed internal mat with black textile brush strips and anthracite anodised aluminium recessed edge strip.



FPC1 - The Street & Living Room areas.

Polished concrete floor with surface treatment.



FC2 - Customer Toilets and Lobby, GF Kitchenette.

Fiandre 'Fjord' 600 x 600 x 8mm porcelain tile – colour: Grey.



FT1 - Sales Consultants and Managers' offices.

Tretford Interlife sheet carpet – colour: 572 Milk Chocolate.



FT2 - First floor offices, meeting rooms and walk-ways.


Tretford Interlife 500 x 500mm carpet tiles – colour: 572 Milk Chocolate.



FC3 - Staff Canteen, Staff Toilets and Technicians Facilities.

Porcelain tile with coved skirtings to match.

Colour: Mid-grey.




FV1 - Stores and alternate option for Staff Canteen, Staff Toilets and Technicians Facilities.


Non-slip sheet vinyl with coved skirtings to match.

Colour: Mid-grey.

Wall finishes



Real wood "Ash" full height, vertical timber batten feature by VCI approved specialist (refer to supplier appendices).



P1 - Paint to walls generally unless specified otherwise and in back of house areas.

Plasterboard walls and exposed steels decorated in emulsion paint matt finish. RAL 9003 Signal White.



P1A - Paint to walls in The Street / Vehicle Display area as indicated within Design Packs.

Matt paint finish to RAL 7044 Silk Grey.

All skirtings and joinery in semi-gloss paint finish to match as appropriate.



P1B - Paint to walls in Consultation Rooms, Sales Consultants and Managers' offices.

Matt paint finish to RAL 7047 Telegrey.


All skirtings and joinery in semi-gloss paint finish to match as appropriate.



P1C - Paint to walls in Car Delivery Bays / Areas.

Plasterboard walls in matt paint finish to RAL 7037 Dusty Grey.


All skirtings and joinery in semi-gloss paint finish to match as appropriate.



WT1 - Wall tiling.

Customer WC areas

Fiandre 'Fjord' 600 x 300 x 8mm porcelain tile – colour: Grey.



M1 - Wall tiling.

Kitchenette, Staff Canteen splash backs, Staff Toilets and Technicians Facilities.

200 x 200mm white tiles to retailer selection.


Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

NB: Please refer to the Outline Specifications for full details

Plan illustration.
Not to scale.



Note: for full specification including dimensions, power, data, audio and media player requirements for each screen please refer to the Supplier Appendices.

VRSE Digital elements

Comprising:


1. Digital Sales Units
2. Internal Selekt Certified Screen
3. Explorer Screen
4. Storytelling Screen
5. Informal Consultation Point Screen
6. Consultation Room Screen
7. Car Delivery Screen.



Digital Sales Units


Internal Selekt Certified Screen


Explorer Screen


Storytelling Screen


Informal Consultation Point Screen


Consultation Room Screen


Car Delivery Screen


Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

NB: Please refer to the Outline Specifications for full details

Plan illustration.
Not to scale.



Key

FD2 - Aluminium framed external scraper mat with black rubber insert and anthracite anodised aluminium recessed edge strip.

FD1 - Aluminium framed internal mat with black textile brush strips and anthracite anodised aluminium recessed edge strip.

FPC 1 - Polished concrete floor with surface treatment.

FC2 - Customer Toilets and Lobby, GF Kitchenette.

Fiandre 'Fjord' 600 x 600 x 8mm porcelain tile – colour: Grey.

FT1 - Sales Consultants and Managers' offices

Tretford Interlife sheet carpet – colour: 572 Milk Chocolate.


Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

NB: Please refer to the Outline Specifications for full details

Plan illustration.
Not to scale.



Key

FT2 - First floor offices, meeting rooms and walkways.

Tretford Interlife 500 X 500mm carpet tile – colour: 572 Milk Chocolate.

FD3 - Optional alternative finish to walkways - heavy duty carpet tile to retailers specification.

Colour: dark grey.

FV1 / VS4 - Stores and alternate option for Staff Canteen, Staff Toilets and Technicians Facilities.

Non-slip sheet vinyl with coved skirtings to match.

Colour: Mid-grey.

FC3 - Staff Canteen, Staff Toilets and Technicians Facilities.

Porcelain tile with coved skirtings to match.

Colour: Mid-grey.

Datasheet 4.2 Finishes / fittings

Do not scale from these drawings

4.2.10 Ground Floor ceiling finishes plan


Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

NB: Please refer to the Outline Specifications for full details

Plan illustration.
Not to scale.



Key

CS6 - The Living Room areas

Proprietary 600 x 1,200mm lay in timber ceiling in real wood 'Ash' ribs.

CS1A - Car Delivery Bays

Painted MF gypsum ceiling. Matt finish to RAL 7037 Dusty Grey.

CT1 - Stores, Canteens and Techs facilities including Staff and Tech toilets

600 x 600mm moisture resistant lay in grid system. Standard white.

CS4 - Consultation Rooms, Offices and Meeting Rooms

600 x 600mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

Ceiling margins where shown to achieve full tile ceiling grids symmetrically set out within the room should be finished as (CS1) painted MF gypsum ceiling. Matt finish to RAL 9003 Signal White.

CS1B - The Living Room areas.

Friezes and bulkheads.

Datasheet 4.2 Finishes / fittings

Do not scale from these drawings

4.2.11 First Floor ceiling finishes plan


Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

NB: Please refer to the Outline Specifications for full details

Plan illustration.
Not to scale.



Key

CS3 - The Street

600 x 1,200mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

CS4 - Offices and Meeting Rooms

600 x 1,200mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

CS1A - Car Delivery Bays

Painted MF gypsum ceiling. Matt finish to RAL 7037 Dusty Grey.

CS1 / CS1B - The Street

Friezes and bulkheads

MF gypsum ceiling. Matt finish to RAL 9003 Signal White.

Alternate colour for the Street friezes and bulkheads where indicated - matt finish to RAL 7044 Silk Grey.

CT1 - Stores, Canteens and Techs facilities including Staff and Tech toilets

600 x 600mm moisture resistant lay in grid system. Standard white.

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Section 4.3

External Details

Datasheet 4.3 External details

Do not scale from these drawings


4.3.1 Shop Windows

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from generic layout plan



Detailed area

Finishes

Proprietary frameless, jointless, double glazed 12mm leaf clear glazed, toughened, low E, low iron, Argon filled cavity glazing in single pane (to nearest, full 1,200mm wide module of glazing over).

Size 6,000 x 2,400mm high overall.

Pre-contract H&S plan to inform contractors of weight and lifting conditions


or


single-glazed, solid, jointless panes are acceptable if SBEM can accommodate heat losses.


NB: Please refer to the Outline Specifications for full details.


Internal window liner to reveals, cill and soffit to frame showroom "Shop Window' internally supplied and installed by Volvo specialist formed with extruded aluminium sections finished to Interpon D2525 – Bleu 2700 Sable – Metallic Fine Texture YW353F.


Shop Window details














Datasheet 4.3 External details

Do not scale from these drawings


4.3.2 Customer Entrance

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location drawing extract from generic layout plan



Detailed area

Finishes

Proprietary Entrance Portal formed with extruded aluminium sections finished to Interpon D2525 – Bleu 2700 Sable – Metallic Fine Texture YW353F with concealed integral flat roof and rain water drainage, LED lighting to front and rear reveals with Opal Acrylic Lens – supplied and installed by Volvo specialist including Opening Hours sign on acrylic plaque to internal side wall.

NB: Contractor to include external scraper matt (FD2) aluminium frame with black rubber insert to external extent of entrance in recessed concrete plinth.

Mat-well edging in proprietary recessed frame set in concrete.

NB: Please refer to the Outline Specifications for full details.

Customer Entrance details



Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Section 4.4

Internal Sales Details

Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.1 General Reception

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All furniture items and fittings to be supplied by either Senab or other VCI approved supplier.

NB: Some construction elements are required in addition to the furniture items.

Please ensure adequate provision is made for power and data requirements in this area.

Reception/Greeter Table recessed Backdrop

Recessed reception/Greeter table backdrop and timber panelled wall areas to The Living Room formed of real wood "Ash" full height, vertical timber batten feature by VCI approved specialist.

Volvo wordmark to plasterboard wall at high level by VCI approved supplier.

Refer to Supplier Appendices.

Finishes

FPC1 - Polished concrete floor.

P1A - Paint to walls in The Street as indicated within the VCI Green Design Packs.

Matt paint finish to RAL 7044 Silk Grey.

P2 - Painted joinery decorated in gloss paint semi matt finish RAL 9003 Signal White.

P2A - Painted joinery decorated in semi-gloss paint, finished to RAL 7044 Silk Grey.

VS1 - Skirtings – 56mm timber (or MDF) skirting lacquer or semi gloss painted RAL 9003 Signal White.

VS1A - 56mm Timber (or MDF) skirting lacquer or semi-gloss painted RAL 7044 Silk Grey.

CS1 / CS1B - The Street - Friezes and bulkheads

MF gypsum ceiling. Matt finish to RAL 9003 Signal White.


Alternate colour for the Street friezes and bulk-heads where indicated - matt finish to RAL 7044 Silk Grey.

CS3 - The Street - 600 x 1,200mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.


CS4 - 600 x 600mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

NB. Please refer to the Outline Specifications for full details.

General Reception plan





Reflected ceiling plan



- A Floor box location
- B Wall mounted socket
- C Feature pendant

Plan and elevation





Comprises:
1. Greeter table
2. Nature box
3. Work table
4. Task chair
5. Curtain.

C Ideal ceiling height

NB: Wherever possible, General Reception ceilings should be 'full height' (i.e. between 4,000 and 5,000mm), unless they are positioned in buildings with lower rooflines, where the minimum height is 2,800mm.

Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.2 Consultation Points

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location drawing extract from generic layout plan



Detailed area

Fittings / fixtures

All furniture items, fittings and loose laid rug to be supplied by either Senab or other VCI approved supplier.

Please ensure adequate provision is made for power and data requirements in this area.

Finishes

FPC1 - Polished concrete floor.

Ceilings typically 4,000 to 5,000mm above FFL.

Brownfield ceiling heights as above to be maximum achievable as GDP.

CS1 - The Street, Friezes, perimeter margins, bulkheads – 'Gyproc Duraline MR' or 'Duraline' painted MF gypsum ceiling, RAL 9003 Signal White, matt finish.

CS1B - The Street

Alternate colour for friezes and bulkheads where indicated - matt finish to RAL 7044 Silk Grey.

CS3 - The Street - 600 x 1,200mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

P1 - Plasterboard walls - Decorated in emulsion paint matt finish RAL 9003 Signal White.

P1A - Paint to walls in The Street as indicated within the VCI Green Design Packs.

Matt paint finish to RAL 7044 Silk Grey.


P2 - Painted joinery - Decorated in gloss paint semi matt finish RAL 9003 Signal White.

VS1 - Skirtings - 56mm timber (or MDF) skirting lacquer or semi gloss painted RAL 9003 Signal White.


VS1A - 56mm Timber (or MDF) skirting lacquer or semi-gloss painted RAL 7044 Silk Grey.

NB: Please refer to the Outline Specifications for full details.


Desk-top height Consultation Point plan




Reflected ceiling plan



High Consultation Point plan



Reflected ceiling plan




A Dark grey square indicates loose laid rug (over tiles)

B Floor box location

A Floor box location


B High Consultation Point digital screen

Plan and elevations




Comprises:
1. Work table
2. Shelving / storage
3. Task chair
4. Visitor chair.

Plan and elevations - High Table version



Plan and elevations - Low Table version



Comprises:
1. Consultation table basic / high
2. Informal Consultation shelving
3. Bar chair
4. Chair.

Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.3 Accessories Hub / Accessorised Vehicle

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location drawing extract from generic layout plan



Detailed area

Fittings / fixtures

All furniture items, fittings and loose laid rug to be supplied by either Senab or other VCI approved supplier.

Please ensure adequate provision is made for power and data requirements in this area.

Finishes

FPC1 - Polished concrete floor.

Ceilings typically 4,000 to 5,000mm above FFL.

Brownfield ceiling heights as above to be maximum achievable as GDP.

CS1 / CS1B - The Street - Friezes and bulkheads

MF gypsum ceiling. Matt finish to RAL 9003 Signal White.

Alternate colour for the Street friezes and bulkheads where indicated - matt finish to RAL 7044 Silk Grey.

CS3 - The Street - 600 x 1,200mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

P1 - Plasterboard walls - Decorated in emulsion paint matt finish RAL 9003 Signal White.

P1A - Paint to walls in The Street as indicated within the VCI Green Design Packs.

Matt paint finish to RAL 7044 Silk Grey.

P2 - Painted joinery - Decorated in gloss paint semi matt finish RAL 9003 Signal White.


P2A - Painted joinery decorated in semi-gloss paint, finished to RAL 7044 Silk Grey.

VS1 - Skirtings - 56mm timber (or MDF) skirting lacquer or semi gloss painted RAL 9003 Signal White.


VS1A - 56mm Timber (or MDF) skirting lacquer or semi-gloss painted RAL 7044 Silk Grey.

NB: Please refer to the Outline Specifications for full details.


Accessories Hub / Vehicle plan



Reflected ceiling plan



Plan and elevations



Comprises:
1. Wheel stand
2. Base stand.

Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.4 Internal Selekt Certified Display

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location drawing extract from generic layout plan



Detailed area

Fittings / fixtures

All furniture items, fittings and loose laid rug to be supplied by either Senab or other VCI approved supplier.

Please ensure adequate provision is made for power and data requirements in this area.

Finishes

FPC1 - Polished concrete floor.

Ceilings typically 4,000 to 5,000mm above FFL.

Brownfield ceiling heights as above to be maximum achievable as GDP.

CS1 / CS1B - The Street - Friezes and bulkheads

MF gypsum ceiling. Matt finish to RAL 9003 Signal White.

Alternate colour for the Street friezes and bulkheads where indicated - matt finish to RAL 7044 Silk Grey.

CS3 - The Street - 600 x 1,200mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

P1 - Plasterboard walls - Decorated in emulsion paint matt finish RAL 9003 Signal White.

P1A - Paint to walls in The Street as indicated within the VCI Green Design Packs.

Matt paint finish to RAL 7044 Silk Grey.

P2 - Painted joinery - Decorated in gloss paint semi matt finish RAL 9003 Signal White.


P2A - Painted joinery decorated in semi-gloss paint, finished to RAL 7044 Silk Grey.

VS1 - Skirtings - 56mm timber (or MDF) skirting lacquer or semi gloss painted RAL 9003 Signal White.


VS1A - 56mm Timber (or MDF) skirting lacquer or semi-gloss painted RAL 7044 Silk Grey.

NB: Please refer to the Outline Specifications for full details.

Selekt Certified Used Display plan




Reflected ceiling plan



- A Floor box location
- B Wall mounted socket
- C Selekt digital screen

Plan and elevations



Comprises:
1. Selekt backdrop
2. Internal Comms Panel.

Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.5 Your Car Studio

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All furniture items, fittings to be supplied by Senab or other VCI approved supplier.

Please ensure adequate provision is made for power and data requirements in this area.

Finishes

FPC1 - Polished concrete floor.

P1 - Plasterboard walls - Decorated in emulsion paint matt finish RAL 9003 Signal White.

P1A - Alternate paint to walls in The Living Room as indicated - matt paint finish to RAL 7044 Silk Grey.

P2 - Painted joinery - Decorated in gloss paint semi matt finish RAL 9003 Signal White.

P2A - Painted joinery decorated in semi-gloss paint, finished to RAL 7044 Silk Grey.

Timber panelled wall areas where indicated formed of real wood “Ash” full height, vertical timber batten feature by VCI approved specialist (refer to supplier appendices).

VS1 - Skirtings - 56mm Timber (or MDF) skirting lacquer or semi gloss painted RAL 9003 Signal White.

VS1A - 56mm Timber (or MDF) skirting lacquer or semi-gloss painted RAL 7044 Silk Grey.

Where this area is located within the higher ceiling height of The Street ceilings will be as per the specification detailed for The Street.

Where this area is located to the underside of the first floor mezzanine ceiling heights are typically 2,800 - 3,000mm above FFL to the specification outlined below.

CS6 - Proprietary 600 x 1.200mm lay in timber ceiling in real wood ‘Ash’ ribs at 20mm thick x 40mm deep and 30mm spacing gap. Lay in timber ceiling to be supplied by VCI approved supplier only.

P3 - Living are soffit behind open ceilings - Ceiling (and all services / ducts) decorated in emulsion paint matt black.

Timber ceilings to be laid with ribs parallel to main approach.

Dropped bulkhead with MF small-tolerance margins can be used to achieve a layout to full tile.


CS1 / CS1B - Friezes and bulkheads

MF gypsum ceiling. Matt finish to RAL 9003 Signal White.


Alternate colour for friezes and bulkheads where indicated - matt finish to RAL 7044 Silk Grey.

NB: Please refer to the Outline Specifications for full details.

Your Car Studio plan




Reflected ceiling plan



A Wall mounted socket

B Pendant light

Components plans and elevations



Comprises:

1. Low or high table with chairs / stools
2. Colour and trims display
3. Display Unit Medium Full Glass
4. Explorer Screen.

Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.6 Consultation Rooms

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location drawing extract from generic layout plan



Detailed area

Fittings / fixtures

All furniture items, fittings to be supplied by Senab or other VCI approved supplier.

Please ensure adequate provision is made for power and data requirements in this area.

Finishes

FPC1 - Polished concrete floor.

CS4 - Consultation Rooms (no less than 2,400mm high)

600 x 600mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

Ceiling margins where shown to achieve full tile ceiling grids symmetrically set out within the room should be finished as (CS1) painted MF gypsum ceiling. Matt finish to RAL 9003 Signal White.

P1B - Paint to walls in Consultation Rooms.

Plasterboard walls in matt paint finish to RAL 7047 Telegrey.

All skirtings and joinery in semi-gloss paint finish to match as appropriate.

V1 - Consultation Rooms


Proprietary 'Komfort Polar' or 'PolarTec' frameless optical white low iron glazed screen and glass door with ironmongery as specified.

All glazing to include manifestation.


All glazed areas to include full length mesh curtains by Senab.

NB: Please refer to the Outline Specifications for full details.

Consultation Room plan



Reflected ceiling plan




A Wall mounted socket

B Floor box location

C Pendant light

Elevations



Comprises:

1. Consultation table
2. Armchair
3. Icon carpet
4. Storage unit
5. Curtain.

Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.7 Lifestyle Shop

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location drawing extract from generic layout plan



Detailed area

Fittings / fixtures

All furniture items, fittings to be supplied by Senab or other VCI approved supplier.

Please ensure adequate provision is made for power and data requirements in this area.

Finishes

FPC1 - Polished concrete floor.

P1 - Plasterboard walls decorated in emulsion paint matt finish RAL 9003 Signal White.

P1A - Alternate paint to walls in The Living Room as indicated - matt paint finish to RAL 7044 Silk Grey.

P2 - Painted joinery decorated in gloss paint semi matt finish RAL 9003 Signal White.

P2A - Painted joinery decorated in semi-gloss paint, finished to RAL 7044 Silk Grey.

Timber panelled wall areas where indicated formed of real wood “Ash” full height, vertical timber batten feature by VCI approved specialist (refer to supplier appendices).

VS1 - Skirtings – 56mm timber (or MDF) skirting lacquer or semi gloss painted RAL 9003 Signal White.

VS1A - 56mm Timber (or MDF) skirting lacquer or semi-gloss painted RAL 7044 Silk Grey.

Where this area is located within the higher ceiling height of The Street ceilings will be as per the specification detailed for The Street.

Where this area is located to the underside of the first floor mezzanine ceiling heights are typically 2,800 - 3,000mm above FFL to the specification outlined below.

CS6 - Proprietary 600 x 1.200mm lay in timber ceiling in real wood ‘Ash’ ribs at 20mm thick x 45mm deep and 30mm spacing gap. Lay in timber ceiling to be supplied by VCI approved supplier only.

P3 - Living are soffit behind open ceilings - Ceiling (and all services / ducts) decorated in emulsion paint matt black.

Timber ceilings to be laid with ribs parallel to main approach.

Dropped bulkhead with MF small-tolerance margins can be used to achieve a layout to full tile.


CS1 / CS1B - Friezes and bulkheads

MF gypsum ceiling. Matt finish to RAL 9003 Signal White.


Alternate colour for friezes and bulkheads where indicated - matt finish to RAL 7044 Silk Grey.

NB: Please refer to the Outline Specifications for full details.

Plan




Reflected ceiling plan



A Wall mounted socket

Components plans and elevations



Comprises:
1. Colour and Trims Display
2. Clothes Hanger
3. Display Unit Medium Full Glass.

Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.8 The Living Room

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location drawing extract from generic layout plan



Detailed area

Fittings / fixtures

All furniture items, fittings to be supplied by Senab or other VCI approved supplier.

Please ensure adequate provision is made for power and data requirements in this area.

Finishes

FPC1 - Polished concrete floor.

P1 - Plasterboard walls decorated in emulsion paint matt finish RAL 9003 Signal White.

P1A - Alternate paint to walls in The Living Room as indicated - matt paint finish to RAL 7044 Silk Grey.

P2 - Painted joinery decorated in gloss paint semi matt finish RAL 9003 Signal White.

P2A - Painted joinery decorated in semi-gloss paint, finished to RAL 7044 Silk Grey.

Timber panelled wall areas where indicated formed of real wood "Ash" full height, vertical timber batten feature by VCI approved specialist (refer to supplier appendices).

VS1 - Skirtings – 56mm timber (or MDF) skirting lacquer or semi gloss painted RAL 9003 Signal White.

VS1A - 56mm Timber (or MDF) skirting lacquer or semi-gloss painted RAL 7044 Silk Grey.

Where this area is located within the higher ceiling height of The Street ceilings will be as per the specification detailed for The Street.

Where this area is located to the underside of the first floor mezzanine ceiling heights are typically 2,800 - 3,000mm above FFL to the specification outlined below.

P3 - Living area soffit behind open ceilings - CS6 - Proprietary 600 x 1.200mm lay in timber ceiling in real wood 'Ash' ribs at 20mm thick x 45mm deep and 30mm spacing gap. Lay in timber ceiling to be supplied by VCI approved supplier only.

P3 - Living are soffit behind open ceilings - Ceiling (and all services / ducts) decorated in emulsion paint matt black.

Timber ceilings to be laid with ribs parallel to main approach.

Dropped bulkhead with MF small-tolerance margins can be used to achieve a layout to full tile.


CS1 / CS1B - Friezes and bulkheads

MF gypsum ceiling. Matt finish to RAL 9003 Signal White.


Alternate colour for friezes and bulkheads where indicated - matt finish to RAL 7044 Silk Grey.

NB: Please refer to the Outline Specifications for full details.


The Living Room - configuration 1



The Living Room - configuration 2



The Living Room - small configuration




Key:


1. Lounge pendant
2. Upholstered sofa
3. Lounge chair - highback
4. Easy chair
5. Lounge tables
6. Lounge floor lamp
7. Storytelling screen
8. Cafe table /chairs.

A Floor box location


Planter units




Plan




Reflected ceiling plan



Plan



Reflected ceiling plan



Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.9 Clean Water Station / Coffee Point

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location drawing extract from generic layout plan



Detailed area

Fittings / fixtures

All furniture items, fittings to be supplied by Senab or other VCI approved supplier.

Please ensure adequate provision is made for power and data requirements in this area.

Finishes

FPC1 - Polished concrete floor.

P1 - Plasterboard walls decorated in emulsion paint matt finish RAL 9003 Signal White.

P1A - Alternate paint to walls in The Living Room as indicated - matt paint finish to RAL 7044 Silk Grey.

P2 - Painted joinery decorated in gloss paint semi matt finish RAL 9003 Signal White.

P2A - Painted joinery decorated in semi-gloss paint, finished to RAL 7044 Silk Grey.

Timber panelled wall areas where indicated formed of real wood "Ash" full height, vertical timber batten feature by VCI approved specialist (refer to supplier appendices).

VS1 - Skirtings – 56mm timber (or MDF) skirting lacquer or semi gloss painted RAL 9003 Signal White.

VS1A - 56mm Timber (or MDF) skirting lacquer or semi-gloss painted RAL 7044 Silk Grey.

Where this area is located within the higher ceiling height of The Street ceilings will be as per the specification detailed for The Street.

Where this area is located to the underside of the first floor mezzanine ceiling heights are typically 2,800 - 3,000mm above FFL to the specification outlined below.

CS6 - Proprietary 600 x 1.200mm lay in timber ceiling in real wood 'Ash' ribs at 20mm thick x 45mm deep and 30mm spacing gap. Lay in timber ceiling to be supplied by VCI approved supplier only.

P3 - Living are soffit behind open ceilings - Ceiling (and all services / ducts) decorated in emulsion paint matt black.

Timber ceilings to be laid with ribs parallel to main approach.

Dropped bulkhead with MF small-tolerance margins can be used to achieve a layout to full tile.


CS1 / CS1B - Friezes and bulkheads

MF gypsum ceiling. Matt finish to RAL 9003 Signal White.


Alternate colour for friezes and bulkheads where indicated - matt finish to RAL 7044 Silk Grey.

NB: Please refer to the Outline Specifications for full details.

Plan




Reflected ceiling plan



- A Floor box location
- B Water supply / drainage (optional)
- C Pendant lights

Components plans and elevations



Comprises:

1. Water station and coffee point
2. Bar chair.

Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.10 Sales Consultants' Office

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location drawing extract from generic layout plan



Detailed area

Fittings / fixtures

All furniture items, fittings to be supplied by Senab or other VCI approved supplier.

Please ensure adequate provision is made for power and data requirements in this area.

Finishes

FT1 - Tretford Interlife sheet carpet – colour: 572 Milk Chocolate.

CS4 - 600 x 600mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

Ceiling margins where shown to achieve full tile ceiling grids symmetrically set out within the room should be finished as (CS1) painted MF gypsum ceiling. Matt finish to RAL 9003 Signal White.

P1B - Paint to walls in Offices.

Plasterboard walls in matt paint finish to RAL 7047 Telegrey.

All skirtings and joinery in semi-gloss paint finish to match as appropriate.

V1 - Offices


Proprietary 'Komfort Polar' or 'PolarTec' frameless optical white low iron glazed screen and glass door with ironmongery as specified.

All glazing to include manifestation.


All glazed areas to include full length mesh curtains by Senab.

NB: Please refer to the Outline Specifications for full details.

Plan




Reflected ceiling plan



A Wall mounted socket

B Floor box or wall mounted sockets location

Elevations



Comprises:
1. Work tables
2. Task chairs
3. Storage units
4. Curtain.

Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.11 Sales / Business Managers' office

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location drawing extract from generic layout plan



Detailed area

Fittings / fixtures

All furniture items, fittings to be supplied by Senab or other VCI approved supplier.

Please ensure adequate provision is made for power and data requirements in this area.

Finishes

FT1 - Tretford Interlife sheet carpet – colour: 572 Milk Chocolate.

CS4 - 600 x 600mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

Ceiling margins where shown to achieve full tile ceiling grids symmetrically set out within the room should be finished as (CS1) painted MF gypsum ceiling. Matt finish to RAL 9003 Signal White.

P1B - Paint to walls in Offices.

Plasterboard walls in matt paint finish to RAL 7047 Telegrey.

All skirtings and joinery in semi-gloss paint finish to match as appropriate.

V1 - Offices


Proprietary 'Komfort Polar' or 'PolarTec' frameless optical white low iron glazed screen and glass door with ironmongery as specified.

All glazing to include manifestation.


All glazed areas to include full length mesh curtains by Senab.

NB: Please refer to the Outline Specifications for full details.

Plan




Reflected ceiling plan



A Wall mounted socket

B Floor box or wall mounted sockets

Elevations



Comprises:
1. Work tables
2. Task chairs
3. Storage units
4. Curtain.

Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.12 Car Delivery Bays

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All furniture items, fittings to be supplied by Senab or other VCI approved supplier.

Please ensure adequate provision is made for power and data requirements in this area.

Finishes

FPC1 - Polished concrete floor.

CS1A - Car Delivery Bays

Painted MF gypsum ceiling. Matt finish to RAL 7037 Dusty Grey.

Ceilings typically 2,800 / 3,200mm above FFL.

P1C - Paint to walls in Car Delivery Bays.

Plasterboard walls in matt paint finish to RAL 7037 Dusty Grey.

All skirtings and joinery in semi-gloss paint finish to match as appropriate.

V1 - Car Delivery Bays


Proprietary 'Komfort Polar' or 'PolarTec' frameless optical white low iron glazed screen and glass door with ironmongery as specified.

All glazing to include manifestation.

All glazed areas to include full length mesh curtains by Senab.

NB: Please refer to the Outline Specifications for full details.


Car Delivery Bay plan




- A Floor box
- B Car Delivery digital screen
- C Wall mounted socket
- D Pendant light
- E Illuminated wall graphic
- Indicates 11kW charger

Comprises:
1. Lounge chair
2. Lounge tables
3. Floor lamp
4. Curtain.

Reflected ceiling plan



Elevations



Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.13 A - Customer Facilities - Toilets

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location drawing extract from generic layout plan



Detailed area

Fittings / fixtures

All fittings to be supplied by VCI approved supplier.

Please ensure adequate provision is made for power requirements in this area.

Fittings

WC and basin suites to be white vitreous china sanware, concealed cistern, basin and satin stainless-steel fittings. WC to be wall hung version.

Single mixer pillar tap in satin stainless-steel.

Accessible toilet to have contemporary Doc M pack in matching white vitreous china and satin stainless steel ironmongery including flush plate, rails and wall brackets.

Mirrors – 600 x 900mm silver backed float glass set in flush with tiled walls.

Wall mounted soap dispensers - satin stainless steel finish.

Hand driers - satin stainless steel finish.

Toilet roll holders, flush plates etc. by D-Line Knud Holscher collection or similar approved– all in satin stainless-steel to match ironmongery finish consistently including pillar taps.

Finishes

FC2 -Fiandre 'Fjord' 600 x 600 x 8mm porcelain tile – colour: Grey.

CS1 - Customer Toilets

Painted MF gypsum ceiling, moisture resistant. Matt finish to RAL 9003 Signal White.

Ceilings typically 2,400mm above FFL.


Internal doors - timber solid core, laminated door in frame with concealed hinges and ironmongery as required. Doors to be HW lipped edge finished to RAL 9003 Signal White.

WT1 - Fiandre 'Fjord' 600 x 300 x 8mm porcelain tile – colour: Grey.


Customer toilet walls to have concealed cisterns.

NB: Please refer to the Outline Specifications for full details.


Customer Facilities - Toilets - plan




Reflected ceiling plan



Elevations - male / female facilities



Elevations - Accessible facilities



Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.13 B - Customer Facilities - Coats Cupboard

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All fittings to be supplied by VCI approved supplier.


Finishes

FC2 -Fiandre 'Fjord' 600 x 600 x 8mm porcelain tile – colour: Grey.

Cupboard doors - timber solid core, laminated door in frame with concealed hinges and ironmongery as required. Doors to be HW lipped edge finished to RAL 9003 Signal White.

NB: Please refer to the Outline Specifications for full details.

Coat Cupboard plan and elevation



Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.14 Front of House Kitchen Facilities & Cleaner's Cupboard

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All furniture items and fittings to be supplied by the Retailer and same to advise contractors.

Please ensure adequate provision is made for power requirements in this area.

Please note that all finishes required to this area are to the Retailer's own specification - those listed below are for reference only.

Finishes

Kitchenette areas to include proprietary wall / sink unit with mixer tap and drainer along with above sink wall storage unit. Carcass to include under counter space for dishwasher and fridge.

CT1 - Suspended Ceiling Tiles - To Kitchenette and Cleaner's cupboard - 'Zentia Hydrabloc' or similar 600 x 600mm moisture resistant lay in grid system.

Ceilings typically 2,400mm above FFL.

M1 - Wall Tiling - 200 x 200mm white wall tile, matt, White grout. Final specification TBC.

FC3 - Kitchenette - 450 x 450mm stone tile with Grey grout or FV1 - vinyl sheet.

Internal doors - timber solid core, laminated door in frame with concealed hinges and ironmongery as required. Doors to be HW lipped edge finished to RAL 9003 Signal White.

Cleaners Cupboard to have cleaners sink with high splash-back and bucket grating in white vitreous china with lever handle taps.

P1 - Paint to walls.


Plasterboard walls in matt paint finish RAL 9003 Signal White.

FVI - Floor to be non-slip vinyl sheet with coved skirtings to match. Colour: mid grey.


Internal doors - timber solid core, laminated door in frame with concealed hinges and ironmongery as required. Doors to be HW lipped edge finished to RAL 9003 Signal White.

NB: Please refer to the Outline Specifications for full details.


Kitchen Facilities Plan




Reflected ceiling Plan



Elevations





Datasheet 4.4 Internal Sales details

Do not scale from these drawings


4.4.15 Front of House Staircase

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

Please ensure adequate provision is made for power requirements in this area.

Finishes

Front of house – Precast (or reinforced) concrete stairs suitably lined (or polished-off shutter) concrete.

Open stringers to be finished with framed glazed balustrading with stainless steel posts and handrails – rails to continue on stairwell walls.

Closed stringers to be finished with stainless steel handrails (min. 50mm dia.) To Brand Guardian approval.

FC2 - Treads to Fiandre 'Fjord' 600 x 600 x 8mm porcelain tile – colour: Grey.

or

FT2 - Tretford Interlife 500 x 500mm carpet tiles – colour: 572 Milk Chocolate.

Proprietary nosings and white painted MDF skirtings to match RAL 9003 Signal White.

CS1 - Ground floor ceiling area.

Painted MF gypsum ceiling. Matt finish to RAL 9003 Signal White.


P1 - Plasterboard walls - Decorated in emulsion paint matt finish RAL 9003 Signal White.

P2 - Painted joinery - Decorated in gloss paint semi matt finish RAL 9003 Signal White.


VS1 - Skirtings - 56mm Timber (or MDF) skirting lacquer or semi gloss painted RAL 9003 Signal White to offices.

NB: Please refer to the Outline Specifications for full details.


Ground Floor Staircase plan




Ground Floor Reflected ceiling Plan





First Floor Staircase plan




Typical plan and Elevations









Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Section 4.5

Internal Staff Area Details

Datasheet 4.5 Internal Staff Area details

Do not scale from these drawings


4.5.1 Staff Toilets

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All furniture items and fittings to be supplied by the Retailer and same to advise contractors.

Please ensure adequate provision is made for power requirements in this area.

Please note that all finishes required to this area are to the Retailer's own specification - those listed below are for reference only.

Fittings

WC and basin suites to be white vitreous china sanware, concealed cistern, basin and satin stainless-steel mixer. tap. WC preferably wall mounted.

Mirrors – 600 x 900mm silver backed float glass set in flush with tiled walls.

Wall mounted soap dispensers - satin stainless steel finish.

Hand driers - satin stainless steel finish.

Toilet roll holders, flush plates etc. – all in satin stainless-steel to match ironmongery finish consistently including pillar taps.

CT1 - Suspended Ceiling tiles to Staff Toilet areas. 'Zentia Hydrabloc' or similar 600 x 600mm moisture resistant lay in grid system.

Ceilings typically 2,400mm above FFL.


M1 - Wall Tiling - 200 x 200mm white wall tile, matt, White grout.

FC3 - Staff toilets - 450 x 450mm stone tile with Grey grout or FV1 - vinyl sheet.


Internal doors - timber solid core, laminated door in frame with concealed hinges and ironmongery as required. Doors to be HW lipped edge finished to RAL 9003 Signal White.

NB: Please refer to the Outline Specifications for full details.


Staff Toilets plan



Reflected ceiling Plan



Plan and Elevations



Datasheet 4.5 Internal Staff Area details

Do not scale from these drawings


4.5.2 Staff Canteen

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All furniture items and fittings to be supplied by the Retailer and same to advise contractors.

Please ensure adequate provision is made for power requirements in this area.

Please note that all finishes required to this area are to the Retailer's own specification - those listed below are for reference only.

Finishes

Canteen areas to include proprietary wall / sink unit with mixer tap and drainer along with above sink wall storage unit. Carcass to include under counter space for dishwasher and fridge.

CT1 - Suspended Ceiling tiles to Staff Toilet areas. 'Zentia Hydrabloc' or similar 600 x 600mm moisture resistant lay in grid system.

Ceilings typically 2,400mm above FFL.


M1 - Wall tiling - 200 x 200mm white wall tile, matt, White grout.

FV1 - Grey sheet vinyl with coved skirting.


Internal doors - timber solid core, laminated door in frame with concealed hinges and ironmongery as required. Doors to be HW lipped edge finished to RAL 9003 Signal White.

NB: Please refer to the Outline Specifications for full details.


Staff Canteen Plan



Plan



Plan and elevations



Datasheet 4.5 Internal Staff Area details

Do not scale from these drawings


4.5.3 eLearning Room

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All furniture items and fittings to be supplied by the Retailer and same to advise contractors.

Please ensure adequate provision is made for power and data requirements in this area.

Please note that all finishes required to this area are to the Retailer's own specification - those listed below are for reference only.

Finishes

FT2 - Tretford Interlife 500 x 500mm carpet tiles – colour: 572 Milk Chocolate.

CS4 - Offices (no less than 2,400mm high)

600 x 600mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

P1 - Paint to walls in Offices.

Plasterboard walls in matt paint finish RAL 9003 Signal White.

All skirtings and joinery in semi-gloss paint finish to match as appropriate.


V1 - Offices

Proprietary 'Komfort Polar' or 'PolarTec' frameless optical white low iron glazed screen and glass door with ironmongery as specified.


All glazing to include manifestation.

NB: Please refer to the Outline Specifications for full details.

eLearning Room Plan




Reflected ceiling Plan



A Floor box or wall mounted socket

Plan and elevations



Comprises:
1. Work table
2. Task chair
3. Storage units
4. Curtain.

Datasheet 4.5 Internal Staff Area details

Do not scale from these drawings


4.5.4 Typical Office

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All furniture items and fittings to be supplied by the Retailer and same to advise contractors.

Please ensure adequate provision is made for power and data requirements in this area.

Please note that all finishes required to this area are to the Retailer's own specification - those listed below are for reference only.

Finishes

FT2 - Tretford Interlife 500 x 500mm carpet tiles – colour: 572 Milk Chocolate.

CS4 - Offices (no less than 2,400mm high)

600 x 600mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

P1 - Paint to walls in Offices.

Plasterboard walls in matt paint finish RAL 9003 Signal White.

All skirtings and joinery in semi-gloss paint finish to match as appropriate.


V1 - Offices

Proprietary 'Komfort Polar' or 'PolarTec' frameless optical white low iron glazed screen and glass door with ironmongery as specified.


All glazing to include manifestation.

NB: Please refer to the Outline Specifications for full details.

Typical Office Plan




Reflected ceiling Plan



A Wall mounted socket

B Floor box

Plan and elevations



Comprises:
1. Work table
2. Task chairs
3. Storage units
4. Curtain.

Datasheet 4.5 Internal Staff Area details

Do not scale from these drawings


4.5.5 Meeting Room

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All furniture items and fittings to be supplied by the Retailer and same to advise contractors.

Please ensure adequate provision is made for power and data requirements in this area.

Please note that all finishes required to this area are to the Retailer's own specification - those listed below are for reference only.

Finishes

FT2 - Tretford Interlife 500 x 500mm carpet tiles – colour: 572 Milk Chocolate.

CS4 - Meeting Rooms (no less than 2,400mm high)

600 x 600mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

P1 - Paint to walls in Offices.

Plasterboard walls in matt paint finish RAL 9003 Signal White.

All skirtings and joinery in semi-gloss paint finish to match as appropriate.


V1 - Offices

Proprietary 'Komfort Polar' or 'PolarTec' frameless optical white low iron glazed screen and glass door with ironmongery as specified.


All glazing to include manifestation.

NB: Please refer to the Outline Specifications for full details.

Meeting Room Plan




Reflected ceiling Plan



A Wall mounted socket

B Floor box

Plan and elevations



Comprises:
1. Meeting table
2. Meeting chair
3. Storage units
4. Curtain.

Datasheet 4.5 Internal Staff Area details

Do not scale from these drawings


4.5.6 Typical Managers' Office

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All furniture items and fittings to be supplied by the Retailer and same to advise contractors.

Please ensure adequate provision is made for power and data requirements in this area.

Please note that all finishes required to this area are to the Retailer's own specification - those listed below are for reference only.

Finishes

FT2 - Tretford Interlife 500 x 500mm carpet tiles – colour: 572 Milk Chocolate.

CS4 - Offices (no less than 2,400mm high)

600 x 600mm RAL 9003 white tile reveal edge, tegular tile. Ceiling grid in white PPC 15mm tee.

P1 - Paint to walls in Offices.

Plasterboard walls in matt paint finish RAL 9003 Signal White.

All skirtings and joinery in semi-gloss paint finish to match as appropriate.


V1 - Offices

Proprietary 'Komfort Polar' or 'PolarTec' frameless optical white low iron glazed screen and glass door with ironmongery as specified.


All glazing to include manifestation.

NB: Please refer to the Outline Specifications for full details.

Plan




Reflected ceiling Plan



A Wall mounted socket

B Floor box or wall mounted socket

Plan and elevations



Comprises:

1. Work table
2. Task chair
3. Visitor chair
4. Storage units
5. Curtain.

Datasheet 4.5 Internal Staff Area details

Do not scale from these drawings


4.5.7 Comms Room

Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

VOLVO

Meda

Location Drawing extract from Generic Layout Plan



Detailed area

Fittings / fixtures

All furniture items and fittings to be supplied by the Retailer and same to advise contractors.

Please ensure adequate provision is made for power and data requirements in this area.

Please note that all finishes required to this area are to the Retailer's own specification - those listed below are for reference only.

Finishes

CT1 - Suspended Ceiling tiles to Comms Room. 'Zentia Hydrabloc' or similar 600 x 600mm moisture resistant lay in grid system.

Ceilings typically 2,400mm above FFL.

P1 - Paint to walls.


Plasterboard walls in matt paint finish RAL 9003 Signal White.

FVI - Floor to be non-slip vinyl sheet with coved skirtings to match. Colour: mid grey.


Internal doors - timber solid core, laminated door in frame with concealed hinges and ironmongery as required. Doors to be HW lipped edge finished to RAL 9003 Signal White.

NB: Please refer to the Outline Specifications for full details.


Plan



Reflected ceiling plan



Plan and elevations



Issued by Volvo Car Ireland.
For additional copies of this Datasheet, a copy of the Outline Specifications or to report any discrepancy, please email **james@experiencemeda.com**

End of Section